c. 1885

Initially called the Saint Inigoes Beneficial Society, the Knights of St. Jerome took its present name on March 1, 1880 thus "uniting together the various beneficial societies into a single order." Ever since it was first conceived, the organization has taken care of the widows and orphans, helped to bury the indigent dead, and care for the sick and disabled. According to current members such as Robert Gant and Vincent Biscoe, the organization has changed little since it was first started. Today, the group offers scholarship money to deserving students wishing to attend college and it holds a number of seasonal barbecues and celebrations. Their meeting hall is the oldest beneficial society hall to remain in continual use in St. Mary's County. Others such as the Love and Charity Society Hall (SM-281) and the Sacred Heart Beneficial Society Hall (SM-282) are no longer used and have fallen into grave disrepair.

On June 12, 1885, the Knights purchased a one acre tract on the northwest corner of Trappe and Old Three Notch Roads for \$30 from Allen C. Tyler.² On September 30 the group held a cornerstone laying celebration at which John Cajay gave a rousing oration concerning equality and religious freedom.³ He was joined on the stage by several trustees of the organization including the group's first president Nicholas Biscoe. The resulting hall was a large two story frame building that was covered with clapboard and a decorative, pressed-tin metal roof. This

¹ Reverend Francis Michael Walsh, <u>Resurrection: The Story of the St. Inigoes Mission: 1634-1994</u> (N.p.: N.p., 1996), 247-250.

² St. Mary's County Land Records, Liber JFF 8, Folio 473-474.

³ St. Mary's Beacon, v 41: 256, p1, c3, 8 October 1885.

Capsule Summary SM-626 Knights of St. Jerome Hall Dameron Private (Page 2)

c. 1885

building immediately became a center point not only for Society functions but also for political meetings and became the site of the parish's first black parochial school.⁴ While the building has been added on to and modified since it was initially built, the hall retains enough historic fabric to communicate its intended function.

⁴ St. Mary's Beacon, v 49: 398, p3, c3, 2 August 1888. See also Walsh, 252.

SM-626, Knights of St. Jerome St. Mary's County Maryland Comprehensive State Historic Preservation Data

<u>Historic Context</u> Geographic Organization: Western Shore

Chronologicial/Developmental Period: Industrial/Urban Dominance, 1870-1930

Historic Period Theme: Architecture

Social/Education/Cultural

Religion

Resource Type Category:

Building

Historic Environment: Rural crossroads

Historic Function and Use: Meeting Hall and School

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory MARYLARS MARKET STATES HISTORIC PROPERTIES

MARYLAND INVENTORY OF

Survey 1	No.	SM-626
----------	-----	--------

Magi No.

DOE __yes __no

1. Nan	ne (indicate pr	referred name)		
historic Kni	ights of St. Jerome			
and/or common	1			
2. Loc	ation			
street & numbe	r 17765 Three Note	ch Rd.	_	not for publication
city, town	Dameron	x vicinity of	congressional district	1
state M	ld	county	St. Mary's TM-68, G-	
3. Clas	ssification			-, -
Category district X building(s) structure site object	Ownership public private both Public Acquisition in process being considered not applicable	Status occupied unoccupied work in progress Accessible x yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence x religious scientific transportation other:
4. Owr	er of Prope	rty (give names ar	nd mailing addresses	of <u>all</u> owners)
name Kr	nights of St. Jerome			
street & number	General Delivery		Robert Gant; telephone no	POCTOT 301-872-4384
	meron		and zip code Md	20628
5. Loca	ation of Leg	al Description	on	
courthouse, regi	stry of deeds, etc. St. Me	ary's County Courthouse		liber JFF 8
street & number				folio 473
city, town	Leonardtown		state	Md
6. Repi	resentation	in Existing	Historical Surve	ys
itle				
date			federal state	county local
lepository for su	rvey records		state	county local
city, town			state	
			31018	

7. Desc	cription	····		Survey No. SM-626
condition excellent	deteriorated	Check one	Check one _X_ original site	

___ moved

date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

_X altered

Contributing Resource Count: 1

_ ruins

_ unexposed

X good

_ fair

The Knights of St. Jerome hall is located in Dameron, Maryland. Lying on the northwest corner of the intersection of Trapp Road and Maryland Rt. 235, the hall is oriented on a north/south axis with its primary elevation facing Trapp Road. The one acre parcel is largely devoid of vegetation as much of the property is planted with grass with the exception of the area immediately in front of the primary elevation which is paved with blacktop. Part of this blacktop area is enclosed by a series of benches that form a small courtyard or square. The property is bounded to the west by a residential lot, to the north by a wooded parcel and on the east and south by roads. A masonry concession stand with a shed roof lies perpendicular to the hall.

The Knights of St. Jerome hall is a two story, frame building with an L-shaped plan. Initially constructed c. 1880, the original building has received several additions over time. This includes a two story addition, an accompanying one story, frame wing, and a one story cinder block addition that extends from the main block.. Much of the building stands on a brick pier foundation, now partially obscured by clapboard siding. The siding is attached to the frame with both wire and fully formed cut nails. The roof of the main block is covered with decorative pressed-metal shingles, while the additions feature asphalt shingle roofs.

The primary or south elevation consists of the main block's side and the gable end of the two story addition. The main block is pierced by a centrally located set of two doors flanked on either side by two, six-over-six, double-hung sash windows. All of these bays are shaded by a hipped porch supported by a series of plain, square posts. This porch extends the full length of the elevation. The second floor is unglazed. A projecting cross-gable sheathed with saw-tooth patterned shingles features a lone six-over-six window. Judging from a difference in the sheathing, a vertical seam between the main block and addition, and a difference in the roof covering, it appears that the two story addition was constructed after the main block. The two story addition is pierced on the first floor by a door. The second floor is pierced by a six-over-six window.

The east elevation consists of the side of the two story addition and one story, frame wing added subsequent to the addition. The addition is pierced on the first and second floors by three six-over-six windows. The wing exhibits a centrally placed panelled door flanked on either side by a six-over-six window. Both the addition and wing feature interior end chimney flues that protrude through the roofs. The wing's chimney is constructed of brick, while the addition's is composed of cinder block.

The north elevation is composed of the wing's gable end and the rear of the main block. The wing is pierced by two, six-over-six windows. The main block also has two six-over-six windows. A one story, unfenestrated, masonry addition extends in a perpendicular direction from the main block.

The west elevation consists of the rear of the one story wing and addition as well as the main block's gable end. The wing has two six-over-six windows and the main block features two unglazed windows situated in the attic. These windows lie on either side of an interior end, cinder block chimney that pierces the roof.

-			Survey No. SM-62	26
preh 1400 1500 1600 1700 1800 1900	0-1499 archeology-historic 0-1599 agriculture 0-1699 _X_ architecture 0-1799 art 0-1899 commerce	heck and justify below community planning conservation economics education engineering exploration/settlement industry invention	Iandscape architectur Iaw Iterature Indicates Indicates Iterature	eX religion sclence sculpture social/ humanitarian theater transportation other (specify)
Specific	dates	Builder/Architect		
check:	T 1 5 5 4 15	BCDE	EFG	

Significance

Prepare both a summary paragraph of significance and a general statement of history and support.

Initially called the Saint Inigoes Beneficial Society, the Knights of St. Jerome took its present name on March 1, 1880 thus "uniting together the various beneficial societies into a single order." Ever since it was first conceived, the organization has taken care of the widows and orphans, helped to bury the indigent dead, and care for the sick and disabled. According to current members such as Robert Gant and Vincent Biscoe, the organization has changed little since it was first started. Today, the group offers scholarship money to deserving students wishing to attend college and it holds a number of seasonal barbecues and celebrations. Their meeting hall is the oldest beneficial society hall to remain in continual use in St. Mary's County. Others such as the Love and Charity Society Hall (SM-281) and the Sacred Heart Beneficial Society Hall (SM-282) are no longer used and have fallen into disrepair.

On June 12, 1885, the Knights purchased a one acre tract on the northwest corner of Trappe and Old Three Notch Roads for \$30 from Allen C. Tyler.² On September 30 the group held a cornerstone laying celebration at which John Cajay gave a rousing oration concerning equality and religious freedom.³ He was joined on the stage by several trustees of the organization including the group's first president Nicholas Biscoe. The resulting hall was a large two story frame building whose walls were covered with clapboard and roof with decorative, pressed metal roof. This building immediately became a center point not only for Society functions but also for political meetings and became the site of the parish's first black parochial school.⁴ While the building has been added on to and modified since it was initially built, it retains enough historic fabric to communicate its intended function.

¹ Reverend Francis Michael Walsh, <u>Resurrection: The Story of the St. Inigoes Mission: 1634-1994</u> (N.p.: N.p., 1996), 247-250.

² St. Mary's County Land Records, Liber JFF 8, Folio 473-474.

³ St. Mary's Beacon, v 41: 256, p1, c3, 8 October 1885.

⁴ St. Mary's Beacon, v 49: 398, p3, c3, 2 August 1888. See also Walsh, 252.

9. Major Bibliographical References

Survey No. SM-626

See Significance 8.0.

O. Geo	graph	ical Data	1		
creage of nominuadrangle name	ated property Point No	.85 acres		Q	uadrangle scale1:24 000
M References	do NOT co	omplete UTM ref			
Zone Eastin	البيا	Northing	B Zone	Easting	Northing
	<u> </u>		D	┧ ┇ ┇ ┇	
		and justification	H L		
erbal bounda	ry description	Jii aliu justiiioutioi			
Same as per de	ed description	on.			
Same as per de	ed description			county bou	
Same as per dec	ed description	on.		r county bou	ndaries code
Same as per dec ist all states tate	ed description	on. s for properties ov	verlapping state o	county bou	
Same as per dec ist all states tate	ed description	on. s for properties ov code	county	r county bou	code
Same as per declist all states tate	ed description	on. s for properties ov code code	county	county bou	code
Same as per declist all states state 11. Foliname/title Kir	ed description and counties The Pre	code code code	county county Surveyor	date 8-1	code
state 11. FOI name/title Kir	ed description and countie m Pre k E. Ranzett Mary's Coun	code code code pared By a, Historic Sites S ty Dept. of Planning	county county Surveyor		code

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust Shaw House 21 State Circle Annapolis, Maryland 21401

(301) 269 2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
-511-7100

SM-626, Knights of St. Jerome St. Mary's County 7.1 Description

The interior was inaccessible at the time of the visit.

The cinder block concession stand is entered via a door located on its south side. The stand has three bays that are used to sell food during events.

SM-626, Knights of St. Jerome

St. Mary's County

8.1 Significance

Chain-of-Title

(All deeds are located at the Land Records Office, St. Mary's County Courthouse, Leonardtown, Maryland unless otherwise noted.)

Reference: Liber JFF 8, Folio 473-474 Grantee: Knights of St. Jerome Society

Grantor: Allen C. Tyler Date: June 13, 1885

Notes: The deed transfers one acre of propery that is bordered by the "public road leading from St. Inigoes Store" and "the old three notch road." Interestingly, a covenant was executed with the deed that stipulated that the property could be put "to no other purpose than for the use and benefit of said Society to hold their meetings and transactions." It also noted that the "proposed house or stall not be converted nor conveyed or sold for the purpose of a dwelling house or any other purpose..."

Reference: Liber JTB 4, Folio 104


Grantee: David W. Tyler

Grantor: William C. and May L. Bayne

Date: December 29, 1862

Notes: Here the tract called "Elizabeth Manor" consists of 108 acres.

S 50 50 -1 -1 -1 1





In place of it works X X Z Z X K K. K. + m. . 44+ 4 1 78.